8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity
	Bund R. L. 55·00 and 6 feet top width		
1	Earthwork to bund	C. yd.	5,049
2	Earthwork breach filling	„	7,623
3	Removing sand silt from breach	„	1,870
4	New stone work	„	1,333
5	Old stone work	„	258
6	Grade stones	No.	28
7	Index stones	„	28
8	Gauge stone (14 feet high)	„	1
9	B. M. stones	„	2
10	Gravel backing behind revetment...	C. yd.	731
11	Turfing	S. yd.	6,205
12	Under pining the old stone revetment	L. S.	Rs.
	Sluice.		
13	Repairing the existing sluice	L. S.	Rs.
	Waste weir 148 feet long at R. L. 55·00.		
14	Earthwork clearing draft and approaches and excavating foundation and the earth used for wing bund and main bund.	L. S.	Rs.
15	Burnt brick in surki mortar	C. ft.	1,448
16	Plastering with surki mortar	Sq. ft.	4·51
17	Burnt stone slabs	„	444
18	Rough stone work apron	C. yd.	219
19	Old stone work	„	73

K. PONNAPPA,
Executive Engineer.

MYSORE DIVISION.

Dated 12th February 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive ...neer, Mysore Division, up to 15th March 1913, for improving the roof of Sandalkoti ...nsur. An approximate estimate of quantities is given below. These quantities are ...aranteed. The work should be completed by the end of May 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engi... Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the ...ive Engineer. The tenders should be accompanied by a statement in the form given ...showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred ... cash or Government Promissory Notes, as earnest money, and be superscribed ... for improving the roof of Sandalkoti at Hunsur," in default of which, tenders will ...ed.

5. The final acceptance of any tender will rest with Chief Engineer, who does not ...self to accept the lowest or any tender or to assign any reason whatever for the ... of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be ... to execute the usual contract bond; in default of which, his tender will be consider... and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be ...he notice board in the Executive Engineer's Office in due course. No enquiries ...the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Improving the roof of Sandalkoti at Hunsur.

No.	Items of work	Per	Quantity
1	Removing the existing roof of pan tiles and bamboo sticks, etc.	Sq.	274·20
2	Teakwood work wrought and put up	C. ft.	213·68
3	Roofing with 1st class Mangalore tiles, teak reepers, etc., complete.	Sq.	274·20
4	Mangalore ridge tiles set in mortar and cement pointing ...	R. ft.	1,240
5	Reconstructing the top of walls with burnt brick in chunam	C. ft.	3,088
6	Chunam plastering	Sq.	477·84
7	White and colorwashing	Do	477·84
8	Flooring with gravel and tamping	C. yd.	149
9	Removing the existing earth flooring and make it one uniform level.	Sq.	40·31
10	Inserting new teakwood work in place of rotten ones during execution.	Lump	sum.

R. V. SUNDARAM IYER,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

"Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 5 P.M., on 8th March 1913, for restoring the Udugani Thosikatte, Registered No. 728—1132, Shikarpur Taluk."

V. R. NIJAGAL,
Executive Engineer.